

भारत सरकार
अन्तरिक्ष विभाग

इसरो दूरमिति अनुवर्तन तथा
आदेश संचारजाल (इस्ट्रैक)

प्लॉट सं. 12 व 13, 3 मेन, 2 फेज
पीण्या औद्योगिक क्षेत्र

बेंगलूर - 560 058. भारत

फैक्स : 91-80-28394249 & 91-80-28094125

दूरभाष : 91-80-28395129 & 91-80-28094000

डीआईडी ग्रुप : 91-80-28094000 to 91-80-28094599

तार : इस्ट्रैक, ई-मेल :



GOVERNMENT OF INDIA
DEPARTMENT OF SPACE
**ISRO TELEMTRY TRACKING
AND
COMMAND NETWORK (ISTRAC)**

PLOT NO. 12 & 13, 3rd MAIN, 2nd PHASE

PEENYA INDUSTRIAL AREA

BANGALORE - 560 058. INDIA.

Fax : 91-80-28394249 & 91-80-28094125

Telephone : 91-80-28395129 & 91-80-28094000

DID group : 91-80-28094000 to 91-80-28094599

GRAMS : **ISTRAC**, E-mail :

NOTICE INVITING QUOTATION No.64

CORRIGENDUM – I dated 14/03/2107

ISTRAC/CMG/C/QTN-64/2016-17

dated 14.03.2017

Name of Work: Conducting Soil investigation at the proposed site of RDA and MEOSAR building at SCC campus, ISTRAC, Bengaluru.

Ref: ISTRAC/CMG/C/QTN-64/2016-17 dated 06.01.2017

Sealed quotations are invited for the work of **Conducting Soil investigation at the proposed site of RDA and MEOSAR building at SCC campus, ISTRAC, Bengaluru**". The quotation shall be addressed to Group Head CMG, ISRO TELEMTRY TRACKING AND COMMAND NETWORK (ISTRAC), Plot No.12 & 13, 3rd Main, 2nd Phase, Peenya Industrial Area, Bangalore- 560058. Quotation shall be submitted on or before 13.03.2017 extended upto 22.03.2017. The quotation shall be opened on 14.03.2017 at 1100 hrs extended upto 23.03.2017 at 1100 hrs at CMG office, SCC Campus, ISTRAC, Bangalore. Period of completion for the work is 15 days.

सं./Encl.: Blank Quotation

सेवा में/To:

M/s.....

.....

समूह प्रधान- सी.एम.जी
Group Head CMG

भारतीय अन्तरिक्ष अनुसंधान संगठन (इसरो)



INDIAN SPACE RESEARCH ORGANISATION (ISRO)

Name of work: Conducting Soil investigation at the proposed site of RDA and MEOSAR building at SCC campus, ISTRAC, Bengaluru.

SCHEDULE OF QUANTITIES

Sl. No	Qty	Description	Rate	Unit	Amount
1	1.00	Charges for mobilization of equipment and testing personnel at the site of work including cost of demobilization charges.		Job	
		Rate in words Rupees ----- ----- Only			
2	4.00	Erection of rig at the required location		each	
		Rate in words Rupees ----- ----- Only			
3		Drilling 150mm dia boreholes using rotary drilling rig in all kinds of soil including conducting standard penetration test (SPT), charges for collecting disturbed and undisturbed soil samples at the site.			
	4.00	a) Up to a depth of 6.00 mtrs from GL or refusal(N100) whichever is earlier.		bore hole	
		Rate in words Rupees ----- ----- Only			
4	2.00	Same as item 3 (a) above but in ordinary rock/weathered rock (0.50m x 4= 2m)		mtr	
		Rate in words Rupees ----- ----- Only			
5	2.00	Same as item 3 (a) above but in Hard rock (0.50m x 4= 2m)		mtr	
		Rate in words Rupees ----- ----- Only			

